

St. Joseph's Care Center

Louisville, Ohio

Mack Industries, Inc. provided and erected the prestressed hollowcore planking for this assisted living facility addition for Gaetano Contractors. Erection for the first floor over the basement took one day and erection of the second floor took only 3 days to help keep the contractor on schedule. The design utilized many unique planks due to the two unusual angles imparted to the building's wrap-around design.

Project Description:

- Two story assisted living facility addition
- 8" Hollow core plank for first and second floor
- 18,400 SF of plank



Building Design:

- 2 floors over partial basement with 2-hr. fire rating
- 36 units plus mechanical rooms, social areas and walk-overs
- Masonry walls and steel frame on footers
- 24' average room spans



Valley City, OH
(330) 483-3111
www.mackconcrete.com

