

Pymatuning State Park

Andover, Ohio

The Willoughby is a preassembled precast concrete restroom building. The building exterior has a simulated barnwood texture with simulated stone on the lower sections, while the roof is a simulated metal ribbed roof texture. The concrete is pigmented and stained to the customer's specifications.

The interior consists of two (2) ADA restroom compartments, male and female. Each compartment has a toilet, lavatory, concealed hand dryer, stainless steel mirror, stainless steel lockable toilet paper dispenser and stainless steel ADA grab bars. Upgrades may include skylights, a stainless steel toilet and lavatory package, exterior stainless steel water fountains, and an exterior frost proof hose bib.

The fully assembled building is set in one day from loading at the plant to delivery installation over pre-installed utility stub ups on the prepared foundation. After the contractor made the final utility connections, the building was ready to use.

Pre-assembled precast restroom buildings provide needed restroom facilities without the extended jobsite interruptions created by normal construction methods, providing customers with an affordable, aesthetically appealing facility that is virtually maintenance free.

"Due to the quick installation of the precast restroom building, the park was not disrupted and was able to stay open during the entire construction process. Also, as the contractor our labor costs were greatly reduced, which adds to the bottom line."

~Easton Excavating Contractors



www.carrconcrete.com

(800) 837-8918

